

NOTES:

- RISER SHALL BE PLUMB.
- VALVE OPERATING NUT SHALL BE CENTERED IN THE RISER AND FULLY ACCESSIBLE.
- MATERIAL BELOW CONCRETE ENCASEMENT SHALL BE COMPACTED TO 95% MINIMUM.
- CONCRETE ENCASEMENT SHALL BE ALLOWED TO CURE 24 HOURS MINIMUM PRIOR TO FINISH PAVING.
- TRIANGULAR LID SHALL POINT IN THE DIRECTION OF THE MAIN WHICH IS ISOLATED BY THE VALVE,

1	VALVE BOX/LID - MARKED 'WATER', DLDCASTLE PRECAST NO. GO4 BOX, GO4C LID
2	CONCRETE ENCASEMENT AROUND VALVE BOX - TYPE II SIX-SACK PORTLAND CEMENT
3	8' RISER - SDR35 ONLY, CONTINUOUS SECTION
4	#10 INSULATED COPPER LOCATOR WIRE



CITRUS HEIGHTS WATER DISTRICT

APPROVED BY:

Polet a. Church CITRUS HEIGHTS WATER DISTRICT

DATE: 5/8/13

WATER MAIN VALVE BOX - STREET/DRIVEWAY

DRAWN: 8 MAY 2013

REVISED:

SCALE: N.T.S.

DESIGN: P.A.D.

CAD FILE VB_811.DWG

VB_811